



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

BEVERLY EAVES PERDUE  
GOVERNOR

EUGENE A. CONTI, JR.  
SECRETARY

August 3, 2011

**NOTICE TO PROSPECTIVE BIDDERS**

**SUBJECT: Addendum #1**

Tip No: ER-2973  
Fed Aid No: STP-000S(425)  
WBS Element No. 3708.3.13  
Construction of Tree Pits with Grates and Landscape Planting along US-1  
(Franklin St.) in Rockingham, Richmond County

Reference is made to the contract proposal previously furnished for the above referenced project.

The following clarifications, changes, additions and/or deletions shall be made to the Contract Proposal and Plans:

1. The following Bidders attended the Mandatory Pre-Bid Meeting on August 2, 2011 and may submit their Proposal at the bid opening:
  - (1) Bryant's Turf and Landscaping, Inc.
  - (2) Country Boy Landscaping, Inc.
  - (3) Southern Garden, Inc.
  - (4) A.L.M Contracting, LLC
  - (5) Taylor Landscaping and Maintenance
  - (6) Staniel Key Landscaping
  - (7) Taylor's Landscaping Service, Inc.
  - (8) Ingle & Son Landscaping, Inc.
2. Clarification: The fourth paragraph under the item of *Tree In Tree Pit With Grate In Frame*.
  - (1) Tree grate frames may be cast iron or fabricated steel and shall be manufactured by the same company furnishing the tree grates specifically for the tree grate size and style chosen.
3. On page 12 of the Contract Proposal under the item of *Tree In Tree Pit With Grate In Frame*, add the following language:
  - (1) Concrete Frame Setting Band shall be dowelled into saw-cut face of existing concrete sidewalk with # 3 rebar at a spacing of 12" minimum 2 ½" below top of walk. Dowels shall be firmly imbedded into sidewalk a minimum of 4inches and protrude into Concrete frame setting band a minimum of 4inches.  
  
Concrete Frame Setting Band shall be reinforced with a single row of #3 rebar centered in the band vertically and horizontally either as two 'L' bent pieces

joined at opposite corners, or four individual side pieces overlapped and joined at corners.

There will be no direct pay for Rebar as it shall be incidental to other items of the project.

4. On sheet L1 of the Plans, revise the caliper of the Muskogee Crape Myrtle trees to 2" min.
5. The items of *Mobilization (Lump Sum)* and *Traffic Control (Lump Sum)* have been added to the Bid Form. A revised Bid Form is attached. The original shall be replaced with this revised sheet.


(1) The lump sum price for *Mobilization* shall be paid in accordance with Section 800 of the *Standard Specifications*.

(2) The lump sum price for *Traffic Control* on the project includes but is not limited to providing **Signs (portable, stationary, barricade or detour), Truck Mounted Impact Attenuators (TMIA), Changeable Message Sign (CMS), Flashing Arrow Panels (FAP), Pilot Vehicle, Flaggers, Cones and Drums** and all labor, tools, equipment and incidentals necessary to furnish, install, maintain and remove traffic control devices when no longer required.

Partial payments will be made on each payment estimate based on the following: Fifty percent of the contract lump sum price bid will be paid on the first monthly estimate and the remaining fifty percent of the contract lump sum price bid will be paid on each subsequent estimate based on the percent of the project completed.

If there are any questions, please contact Jeff Stroder, PE, Division Proposals Engineer at (910) 944-2344 or [jstroder@ncdot.gov](mailto:jstroder@ncdot.gov).

Sincerely,

A handwritten signature in black ink, appearing to read "Timothy Johnson", with a stylized flourish at the end. To the right of the signature is a small, rectangular stamp with the letters "JA3".

Timothy Johnson, PE  
Division Engineer

TJ/JAS

Attachments

cc: Mr. S. L. Ingold Mr. J. A. Stroder, PE

# North Carolina Department of Transportation

## PURCHASE ORDER CONTRACT BID FORM

TIP Number: ER-2973

Work Order Number: 3708.3.13

Landscape planting along US-1 (Franklin St.)

Richmond County

ITEM	ACTIVITY NUMBER	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	AMOUNT BID
1	4101000	MOBILIZATION	1	LS		
2	SP	TRAFFIC CONTROL	1	LS		
3	SP	MUSKOGEE CRAPE MYRTLE STANDARD IN TURF AREA, MATCHED SPECIMEN, SINGLE STEM TO 5' HT, INCLUDING MULCH AND WATER	4	EA		
4	SP	MUSKOGEE CRAPE MYRTLE STANDARD IN TREE PIT WITH GRATE AND FRAME, MATCHED SPECIMEN, SINGLE STEM TO 5' HT, INCLUDING ALL INCIDENTALS	29	EA		

***TOTAL BID FOR PROJECT:*** \_\_\_\_\_

CONTRACTOR \_\_\_\_\_

ADDRESS \_\_\_\_\_

Federal Identification Number \_\_\_\_\_ Contractors License Number \_\_\_\_\_

Authorized Agent \_\_\_\_\_ Title \_\_\_\_\_

Signature \_\_\_\_\_ Date \_\_\_\_\_

Witness \_\_\_\_\_ Title \_\_\_\_\_

Signature \_\_\_\_\_ Date \_\_\_\_\_

**CORPORATE SEAL**